


General Assembly Procedure Hydraulic Mining Shovel PC3000-6



All stated information corresponds to the present development and is subject to possible future changes without prior notice.

GENERAL CONTENT	PAGE
1. General	5
1.1 Delivery of the Excavator	5
1.2 Assembling of the Excavator	5
1.3 Transportation and Lifting.....	7
1.4 Manpower / Assembly Time*	9
1.5 Assembly Site Requirements	11
1.6 Space and Placing Requirements	15
1.7 Preparation for Assembly	15
1.8 Basic Measurements (Z 24015)	17
1.9 Transport Dimensions and Weights (as example).....	17
1.10 Illust. Configuration of Components on Erection Site	19
2.0 Assembly sequence	19
2.1 Assembly of Undercarriage (Z 24016; Z 24017; Z 24018)	21
2.1.1 Assembly	21
2.1.2 Determination of the tightening torque	25
2.1.3 Final works	29
2.2 Assembly of Superstructure onto the Undercarriage (Z 9031a).....	31
2.3 Mounting of Boom and Boom cylinders(Z 9032; Z 20949).....	35
2.4 Mounting of Fuel Tank (Z21924).....	37
2.5 Mounting of Hydraulic access Ladder (Z 24022)	39
2.5 Mounting of Cab Base (Z 24023).....	41
2.6 Mounting of Counterweight (Z 24024)	43
2.7 Mounting of Handrails, Steps and Gratings (Z 24025).....	45
2.8 Mounting of Cab (Z 24029).....	47
2.9 Pre-checks prior Initial Start up.....	49
2.10 Mounting of Stick	53
2.10.1 Backhoe Attachment (Z 24030)	53
2.10.2 Bullclam Bucket Attachment (Z 20950; Z 20951; 20952).....	55
2.11 Assembly of the bucket to the stick.....	61
2.11.1 Assembly of the backhoe to the stick (Z 23005)	61
2.11.2 Assembly of the bullclam bucket to the stick (Z 20953)	63
2.12 Mounting of the Pin Seals.....	67
2.12.1 Backhoe (Z 23006).....	67
2.12.2 Bullclam bucket (Z 21963)	69
2.13 Putting the Central Lubrication System into operation (Z 24031)	71
2.14 Standard Application Torque Chart.....	73
2.14.1 Metric standard thread	73
2.14.2 Metric fine thread	75
2.14.3 Torque Chart for Flange Joints	76

1. General

1.1 Delivery of the Excavator

The excavator is being delivered disassembled into its main components. For the correct dimensions and weights please refer to the packing list of your machine.

For assembling the excavator follow the instructions in this manual.

1.2 Assembling of the Excavator



- **Personnel entrusted with work on the machine must have read the Assembly Manual, the Operation,- Lubrication- and Maintenance Manual and in particular the section on safety before beginning work. Reading the instructions after work has commenced is too late.**

If there are any questions concerning the assembling procedure, contact your local Service Center.

Prior to first operation, inspect the excavator thoroughly with the Service Engineer responsible for the erection of the machine. Check all fluid levels according to the Lubrication and Maintenance Schedule. Damages and defects caused by incorrect operation and maintenance are not covered by the manufacturers guarantee.



- **If the excavator is equipped with a fire suppression system, make sure that the system is ready for operation.**



- **Before assembling/disassembling, lifting or transporting this excavator contact your local Service Center for all the necessary instructions for safe and economic assembling/disassembling, lifting and transportation procedures of your excavator.**

The sequence of assembly as shown in this Manual. Disassembling is basically the reverse order of the assembling procedure.

1.3 Transportation and Lifting

The transport dimensions and weights of the excavator's components are listed in this manual are for general information only. For the correct dimensions and weights please refer to the packing list of your machine.

Observe the operating permits of the low-bed trailers used for transportation. They contain the permissible load, loading width and height.



- **Observe the federal, state and local laws and regulations for transportation of heavy units. Know the safety rules and laws before you transport this Excavator.**
- **Make sure the flat-bed trailer and the components of the Excavator are equipped with the correct safety devices.**
- **Secure the Excavator and all components transported on the trailer against movement.**
- **Use exclusively approved handling equipment.**
- **When lifting components make sure that the handling elements do not cause damage to the component.**
- **Secure the components safely before removing the lifting straps, ropes or chains.**



- Wear safety clothing, goggles, respirator and other safety devices, whenever working conditions make this necessary.
- Provide hoists of sufficient capacity to lift heavy units. Refer to the weight specifications.
- Be sure to observe the instructions in the "Assembly Procedure Manual".
- Lifting gear, tools and other suspension systems must be in good condition and of sufficient lifting capacity.
- Be sure hydraulic cylinders and attachment components are properly supported from hoist and securely fastened, before removing supporting pins.
- Floors must be clean and dry. After draining operations be sure all spillage is cleaned up.

1.4 Manpower / Assembly Time*

	Customer	1 Electrician 4 Fitters/ Mechanics
Supervision	Dealer or Komatsu Mining Germany	1 Service Engineer

	Days
Assembly Time*	6**

*Dependent on mine conditions (shifts, weather, ...)

**Without testing and customer acceptance.

1.5 Assembly Site Requirements

Assembly Site Requirements:

- Well leveled and compacted ground approx. 150 x 150 ft/50 x 50 m
- A container to store the tools, to keep the paper work and for sheltering
- 2 mobile cranes 90 metric tons
- 1 small crane, load capacity approx. 25 metric tons

No.	Qty.	Specification	Designation
1	01	6 metric tons	Telescopic fork lift
2	04	6 metric tons	Chain pull
3	04	35 metric tons	Shackles
4	04	5 metric tons t	Shackles
5	04	1 metric ton	Shackles
6	04	each M10/12/14/16/18/20	Eye bolts
7	04	30 metric tons - 8 m length	Ropes
8	04	25 metric tons - 8 m length	Ropes
9	04	16 metric tons - 8 m length	Ropes
10	04	12 metric tons - 8 m length	Ropes
11	01	∅ 50 mm x 1000 mm length	Pry bar
12	01	∅ 50 mm x 2000 mm length	Pry bar
13	01	5 kg	Large hammer
14	60	300 x 300 x 1000 mm	Wooden blocks
15	10	300 x 300 x 2500 mm	Wooden blocks
16	02	10 metric tons	Hydraulic jacks
17	02	50 metric tons	Hydraulic jacks
18	01	50 m	Cable drum
19	01	each 6/7/8/9/10/12/13/14/15/17/19 mm 22/24/27/30/32 mm	Combination spanner
20	01	each 41/46/50/55/60/ 65 mm	Single ended open spanner
21	01	each 7 mm up to 55 mm	Double end open spanner
22	01	3/4"	Impact wrench
23	01	1/2"	Impact wrench
24	01	1/2"	Ratchet
25	01	3/4"	Ratchet
26	01	each 13 mm up to 19 mm	Sockets for 1/2" Ratchet
27	01	24 mm up to 36 mm	Socket for 3/4" Ratchet
28*	01	Only useable with torque wrench (PN793 374 73) (refer to page 28)	Tightening tool for bolts center section side frame connection (PN793 376 73) including special tightening nut This tool is required to ensure: - that the reaction torque is supported at the bottom of the neighbor bolt - that no bending moment effects the neighbor bolt
29	01	0 – 9900 Nm (refer to page 28)	Hydraulic torque wrench (PN793 374 73)
30		1.2 l; till 700 bar (refer to page 28)	Electric hydraulic power pack (PN793 375 73)

Yazaki Connector Set			
No.	Qty.	Designation	Part No.
1	2	Connector 3-pole	891 040 40
2	2	Connector 3-pole	891 032 40
3	2	Connector 2-pole	891 039 40
4	2	Connector 2-pole	891 031 40
5	2	Connector 1-pole	891 038 40
6	2	Connector 1-pole	891 030 40

	Qty.	Specification	Designation
31	01	30/32/36/41/46/55/65/75 mm	Sockets HD for hydr. torque wrench
32	01	Range 0 - 250 Nm	Torque wrench ⇒ drive 1/2"
33	01	Range 250 - 600 Nm	Torque wrench ⇒ 3/4"
	01	Range to 140 Nm	Cordless Impact Wrench 1/2 " P/N 793 828 73
34	01		Hand drill
35	01	5, 6, 8, 10, 12, 14 mm	Screw driver sockets for 1/2" drive
36	01	14, 17, 19 mm	Screw driver sockets for 3/4" drive
37	01	2 up to 19 mm	Hex keys (Allen keys) L-type
38	01		Electric welding machine
39	01		Lights for the illumination of the working area
40	01		Hand lamp
41	07	600 bar	Pressure gauge
42	03	60 bar	Pressure gauge
43	03	25 bar	Pressure gauge
44	01	15 bar	Pressure gauge
45**	02		Multi-meter P/N 232 619 40
46	02		Cable set P/N 232 496 40
47	01	0 - 2500 min-1	Contact less revolution indicator
48	02	1,5 mm ² 30 m	Cables with connectors
49	01	from M6 - M 36	Thread cutting set
50	01		Level gauge
51	01		Test adapter proportional/solenoid valves P/N 232 537 40 / 232 538 40
52	01	Set	Yazaki connectors (refer to table)
53	01	Set	Screw driver
54	01		Side cutter
55	01		Tip plier
56	01		Combination plier
57	01		Pipe plier

*



- If the specific tool and the prescribed assembly procedure are not used for assembling the crawler carriers to carbody KMG will not carry the warranty for the undercarriage!

** If available an electronic testing device for pressure, voltage and RPM, similar Hydrotechnic System 6000

1.6 Space and Placing Requirements

On the following page, the components are indicated in their approx. dimensions.

They are unloaded in a way that a min. space of 1 meter (3 ft) is left between the components, and that there is enough space for the trucks and the cranes.

1.7 Preparation for Assembly

Unload all components so that no more move is necessary!



All pins, bushings, borings, bearings and contact surfaces of components must be clean

Torque values are listed in section 6.9 of the Lubrication- and Maintenance Manual - unless being listed in this Assembly Procedure Booklet.

Obey all applicable safety and local regulations strictly!

Ensure correct lifting procedures and ensure use of adequate lifting gears!

High voltage installation works must be carried out by authorized specialists only.





Z 24015

1.8 Basic Measurements (Z24015)

1.9 Transport Dimensions and Weights (as example)


Colli No.		ea.	Kind of Packing	Dimensions in cms			Volume in m ³	DESCRIPTION	Weights (kgs)	
				L	W	H			NET	GROSS
1	1	1	unpacked	793	175	221	30,669	crawler side-frame w/800-mm tracks	31.900	31.900
2	1	1	unpacked	793	175	221	30,669	crawler side-frame w/800-mm tracks	31.900	31.900
3	1	1	unpacked	361	402	215	31,201	carbody	19.500	19.500
4	1	1	unpacked	795	540	370	158,841	superstructure with engine	64.000	64.000
5	1	1	unpacked	505	286	80	11,554	counterweight	27.650	27.650
6	1	1	unpacked	225	165	280	10,395	fuel tank	2.400	2.400
7	1	1	unpacked	214	195	265	11,058	cab base	3.100	3.100
8	1	1	case	350	240	300	25,200	accessories	2.700	3.800
9	1	1	case	577	249	188	27,011	accessories	3.100	5.100
10	1	1	case	487	129	148	9,298	2 stick cyl.	5.000	5.600
11	1	1	case	487	129	148	9,298	2 bucket cyl.	3.700	4.300
12	1	1	unpacked	930	251	284	66,294	8.60 m boom w/o cylinders	22.750	22.750
13	1	1	unpacked	567	201	210	23,933	4.00-m stick compl.	11.500	11.500
14	1	1	unpacked	350	332	310	36,022	15.0-cu.m. backhoe bucket	16.100	16.100
15	1	1	unpacked	281	192	245	13,218	cab guard	1.350	1.350
16	1	1	case	487	129	148	9,298	2 boom cyl.	6.100	6.700
							Total m³ -->		252.750	257.650
							503,960	Total Weights kgs -->		




1.10 **Illust. Configuration of Components on Erection Site**

2.0 **Assembly sequence**

	Subject	Illustr.	Page
1.	Assembly of Undercarriage	(Z 24017)	21
2.	Assembly of Superstructure onto the Undercarriage	(Z 9031a)	31
3.	Mounting of Boom and boom cylinders	(Z 9032)	35
4.	Mounting of Fuel Tank	(Z 21924)	37
5.	Mounting of Hydraulic access Ladder	(Z 24022)	39
5.	Mounting of Cab Base	(Z 24023)	41
6.	Mounting of Counterweight	(Z 24024)	43
7.	Mounting of Handrails, Steps and Gratings	(Z 24025)	45
8.	Mounting of Cab	(Z 24029)	47
10.	Mounting of Stick /Stick cylinders	(Z 24030)	51
11.	Assembly of the bucket to the stick	(Z 23005)	59
12.	Mounting of the Pin Seals	(Z 23006)	65
13.	Putting the Central Lubrication System into operation	(Z 24031)	69



Z 24017



Z 24016

2.1. Assembly of Undercarriage (Z 24016; Z 24017; Z 20418)

2.1.1 Assembly


1. Align right side frame horizontally in both directions very exactly. From outside place water level gauge onto steel structure of side frame.
2. Clean the flange areas metallically blank (free of oil, grease; paint; ..)
3. Attach carbody to the crane (oil supply lines to the travel motors pointing in direction of the travel motors).



- **Insert the corresponding lines for the chain tensioning system before installing the side frame.**

4. Align carbody with the side frame.
5. Lubricate all bolts (M48) (head supporting surface and thread) with International Compound No. 2 (PN 324 969 40).
6. Insert the bolts (2 x 18 pieces + 2 measuring bolts)* with a resilient sleeve and tighten with 2100 Nm.
7. Support carbody with wooden blocks in a way that the free side is approx. 200 mm higher than the attached side. (This makes it easier to attach the 2nd side frame).


*Insert the 2 measuring bolts (1) at the upper corners!



Z 24018

8. Clean the flange areas of the second side also metallicity blank (free of oil, grease; paint; ...).
9. Lift the 2nd side frame with the crane and align with the carbody.
10. Insert the bolts (2 x 18 pieces + 2 measuring bolts)* with a resilient sleeve and tighten with 2100 Nm.
11. Lift the undercarriage so far that it is possible to remove the wooden blocks.

*Insert the 2 measuring bolts(1) at the upper corner - refer to drawing (Z 24016)!



Z24019

2.1.2 Determination of the tightening torque

The required tightening torque for **all fastening bolts** has to be determined with the 4 measuring bolts (7), which dimension is analogous to the fastening bolts.

The required axial tension force of the bolts is determined by means of the elongation of the fastening bolts.


The tightening torque must be determined at the first assembly of the excavator at the operation site and for the first inspection and after 1000 operation hours.

The required measuring device (PN 92847640) is delivered with the excavator. To determine the tightening torque, 4 specially prepared measuring bolts are supplied besides the normal fastening bolts. The measuring bolts can be recognized at the machined area at the end of the bolt.


The measuring device is composed of the following items and will be delivered with each new machine (refer to drawing Z 24020).

Procedure to determine the tightening torque for the first assembly (pre-condition side frame is assembled and bolts tightened to 2100 Nm)

1. Loosen all 4 measuring bolts. Do not lubricate the measuring bolts again.
2. Tighten the 4 measuring bolts with 150 Nm.
3. Install the measuring device (refer to drawing Z 24020a).
4. Adjust the dial gauge to the zero position.
5. Install the special hydraulic torque wrench (Z 24021; PN 79337473 + 79337673).
6. Adjust the pressure at the hydraulic torque wrench to 2100Nm and tighten the measuring bolt.
7. Increase the pressure further by steps of 10 bar until the **required elongation of 0.93 mm** of the measuring bolts is reached.
8. List the pressure and the change of the bolt length in a table.
9. Repeat this procedure for all 4 measuring bolts.
10. Add all 4 determined hydraulic pressures and then divide by 4.
11. With this average pressure tighten all other bolts.



Section B - B



Z 24020

Procedure to determine the tightening torque for inspection after 1000 operating hours

1. Loosen all 4 measuring bolts. Do not lubricate the measuring bolts again.
2. Tighten the 4 measuring bolts with 150 Nm.
3. Install the measuring device (refer to drawing Z 24020).
4. Adjust the dial gauge to the zero position.
5. Install the special hydraulic torque wrench (Z 24021; PN 79337473 + 79337673).
6. Adjust the pressure at the hydraulic torque wrench to 2100Nm and tighten the measuring bolt.
7. Increase the pressure further by steps of 10 bar until the required elongation of 0.93 mm of the measuring bolt is reached.
8. List the pressure and the change of the bolt length in a table.
9. Repeat this procedure for all 4 measuring bolts.
10. Add all 4 determined hydraulic pressures and then divide by 4.
11. Now only loosen one of the other bolts and tighten up to the determined average pressure.
12. Repeat this procedure for all the other bolts step by step.




- Do not lubricate the bolts again.
- Do not loosen more than one bolt at the same time.

Measuring Device (PN 928 476 40) (Z 24020a)

Position	Part name	Part No.	Number
1	Angle bar	928 475 40	1
2	Dial gauge	092 706 40	1
3	Screw M5x16	502 515 98	1
4	Feeler	477 172 40	1

5	Bolt M10x25	307 777 99	2
6	Washer	517 122 98	2
7	Measuring bolt	933 613 40	4



Special torque wrench assy. in operation



PN79337673

PN79337473

Parts of the torque wrench



PN79337573

Electro-hydraulic pump set

Z24021


2.1.3 Final works

1. Connect hose pipes between the oil supply lines of the carbody to the travel motors.
2. Open the cocks inside the side frames for the hydraulic crawler tensioning system (refer to the Maintenance Manual).



- **Do not open the cocks before all hydraulic lines are connected with the rotary joint. The lines in the side frame are under pressure!**

3. Fill up and/or check the gear oil levels (travel gear, brake, final drive - refer to the Maintenance Manual).



Z 9031a

2.2 Assembly of Superstructure onto the Undercarriage (Z 9031a)



- **Hang the superstructure platform horizontally at the cranes.**

1. Attach the superstructure to the cranes, lift up the superstructure and carefully clean the surface (contact area) of the slew ring. Clean very carefully the contact surfaces of the slew ring and the carbody.
2. Check if the “S” position of the inner and outer ring of the slew ring is left and right of travel direction.
3. Prepare all bolts (03), sleeves (02) and lubricate the threads as well as the head surface of the bolts, also clean off any paste of the bolts (Refer to Service Bulletin AH00511b!).



- **Remove the cam of the rotary joint before install the superstructure.**





- **Install 2 threaded pins (M30 x 100 mm long, one end pointed, to be manufactured) displaced by 180° to slew ring at superstructure.**

This simplifies the alignment of the slew ring to the undercarriage.



4. Align superstructure to the carbody and lower the superstructure as required to insert 4 bolts.
5. Insert one bolt at each 90° (for guiding) and lower superstructure so that there is a very thin gap between slew ring and carbody.
6. Install all bolts and tighten hand tight.
7. Tighten the bolts crosswise with the required torque. (Refer to Service Bulletin AH00511b).



- **If approx. 10 bolts (front and rear) are tightened the superstructure can be unhooked from the crane.**



Z 9032



Z 20949

2.3. Mounting of Boom and Boom cylinders(Z 9032; Z 20949)



- For the mounting of the pin seals please refer to page 65.
- We recommend mounting stick cylinders to the boom before installing the boom.

1. Lift the boom with the stick cylinders and boom cylinders attached.
2. Align the boom with the boom bearings of the superstructure.
3. Lower the boom that the borings of the boom and the boom bearings are aligned.
4. Insert the two pins (01) and secure with the retainers (02)

The boom must be still attached to the crane!

5. Lift one boom cylinder with an other crane or chain pull and disconnect the transport fastenings.
6. Lower the boom cylinder until the boring of the cylinder and the superstructure bearings are aligned.





- **If necessary lower or raise the boom for easier alignment.**

7. Insert the pin (03) and secure with the retainer (04).
8. Fix the 2nd cylinder in the same manner.
9. Connect the pipes resp. hoses for the boom, stick and backhoe cylinders as much as possible. Unhook boom from the crane.





- **The boom may be unhooked earlier but be careful and pay attention while opening the hydraulic lines. There may be still a little pressure in the system. Therefore be careful when opening the hoses.**




2.4. Mounting of Fuel Tank (Z 21924)

1. Lift the fuel tank.
Lifting eyes are delivered with the machine.
2. Align the fuel tank with the superstructure.
3. Lower the fuel tank fully down and install all bolts. Tighten the bolts with the resp. torque.
4. Connect fuel lines and electric cables.



52



1

Z 24022


2.5 Mounting of Hydraulic access Ladder (Z 24022)

1. Install the platform (1) with 8 bolts(45) – M24x130 and the sleeves (46).
2. Install the appendant handrails (2).
3. Mount the hinged ladder according to “Detail A”

Position Designation


47	Hydraulic cylinder
49	Pin
50	Washer
51	Cotter pin
52	Self locking nut
54	Bearing assy.

4. Tightening Procedure for Self Locking Nuts (52):
Screw on the nuts until they have contact with the ladder carrier frame.
Then tighten the nuts further by turning them through an angle of 45° (1/8 turn).
5. Lubricate both eyes of hydraulic cylinder (47). Make sure both pivot pins (49) are properly secured with cotter pins.
6. Connect the hydraulic hoses to the cylinder.
7. Connect the Accumulators (54) inside the platform (1).



2.5. Mounting of Cab Base (Z 24023)

1. Lift the cab base.
Lifting eyes are delivered with the machine.
2. Align the cab base with the superstructure.
3. Lower the cab base fully down and install all bolts. Tighten the bolts with the resp. torque.
4. Connect electric cables according to the Electric Circuit Diagrams of the machine.




Z 24024

2.6. Mounting of Counterweight (Z 24024)

1. Lift the counterweight.
2. Clean surfaces "A" absolutely free of dirt; oil; fat and paint (metallic clean).
3. Align the counterweight with the superstructure.
4. Lower the counterweight fully down and fasten it with the bolts and washers (01 + 02). Tighten the bolts with the resp. torque.



- **Apply Paste „Optimol White“ PN 999 039 on heads and threads of the bolts (01).**






Z24025

2.7. Mounting of Handrails, Steps and Gratings (Z 24025)

1. During this stage of assembly the handrails, steps and gratings can be mounted to the superstructure, cab base and machinery house.
This provides more safety during further assembly.




Position	Designation
19	Pair of half clamps
20	Cover plate
21	Bolt
22	Washer
23	Nut
24	Bolt
25	Locking plate



Z 24029

2.8. Mounting of Cab (Z 24029)

1. Lift the cab.
Lifting eyebolts are delivered with the machine.
2. Align the cab with the cab base.
3. Lower the cab fully down and fasten the cab with bolts (1)
M16x2 and sleeves (02).
4. Connect electric cables and the hydraulic hoses.
5. If the machine is equipped with an air conditioner, connect the
air hoses and cables.
6. Mount the handrails to the cab if not yet done.



Normal working position	
1	open
2	closed
3	open

Z 20371a

2.9 Pre-checks prior Initial Start up


Engine commissioning



- **The local working safety rules must be strictly observed.**
 - **Only service personnel necessary for first start up testing are allowed to be on the excavator.**
 - **The operator must have read and understood the operation manual.**
 - **Remove all tools and other not fixed material from excavator especially from moving parts.**
-
- Be sure that all hand rails, catwalks and steps etc. are correctly installed.
 - Make sure that all hoses and electrical connections are correctly established (refer to the electrical and hydraulic circuit diagrams). Ex works, all disconnected hose lines and electrical cables are marked with identification numbers.
 - Fill up the hydraulic oil tank and the fuel tank *.
 - Check all fluid levels and correct if necessary *.
Fill up or use filled respective grease container for the Central lube system and the Swing circle lube system *.
 - Make sure that the shut off valve between the main hydraulic tank and the suction tank is completely open.
 - Bleed the engine fuel lines and filters.
 - Bleed the suction side of each main pumps *. Use adequate receptacle to collect out flowing oil. Be sure that the plug seal is in good condition. Tighten the plug securely.
 - Fill up each main pump housings with hydraulic oil *.
 - Bleed pump housing of the fan piston pump *.
 - Check to make sure that the pressure relief cock for the hydraulic track tensioning system are CLOSED and the shut-off cocks in the crawler carriers are OPEN (refer to Illust. Z20371a).
 - Open all lowering throttle valves of working attachment. At works are all closed. Do not forget to adjust the throttle valves after complete mounting of the attachment
(Refer Service Bulletin AH02518 last edition).

Now the engine can be started and the machine can be operated for any additional assemblies. During and after starting pay attention to the instructions in the Operation Manual.

*(Refer to the next pages.)



Z 25014




HYDRAULIC SYSTEM - Vent Hydraulic Pumps (Z25014)

1. Loosen vent plug (A) of suction oil reservoir (1).
Retighten vent plug (A) when the out flowing oil is free of air bubbles.
2. Vent main pump (2) by loosening leakage oil line connector(B) and by opening vent valve (C). Retighten (B and C) when the out flowing oil is free of air bubbles.
3. Vent main pump (3) by loosening leakage oil line connector(B) and by opening vent valve (C).
Retighten (B and C) when the out flowing oil is free of air bubbles.
4. Vent oil cooler fan drive pump (4) by loosening leakage oil line connector (D). Retighten (D) when the out flowing oil is free of air bubbles.
5. Vent control oil pump (5) by loosening vent plug (E) at the suction line flange. Retighten (E) when the out flowing oil is free of air bubbles.
6. Vent main pump (6) by loosening leakage oil line connector(F) and by opening vent valve (G). Retighten (F and G) when the out flowing oil is free of air bubbles.
7. Check hydraulic oil level and the whole hydraulic system for leakage.

REMARK

After changing the oil of the PTO gear vent the PTO lubrication pump (7) by opening vent plug (H) at the suction hose flange.

Retighten (H) when the out flowing oil is free of air bubbles.



Z 24030

2.10 Mounting of Stick

2.10.1 Backhoe Attachment (Z 24030)

1. Lift the boom with the excavator hydraulic.
2. Lift the stick by a crane in nearly vertical position.
3. Lower the stick until stick and boom borings are aligned.
4. Insert pin (1) with mounting sleeve* (2).
*Protection cap for the thread
5. Remove the mounting sleeve (2).
6. Install a whirl (M20) in the nut (5).
7. Lift the final cap (3) with a crane, tilt it and turn it on the pin (1) by using the nut (4) (M30).
8. Secure the cap as shown with the bolt (6).
9. Secure the bolt (6) with the cotter pin (8).
10. Install the stick cylinders to the stick.
11. Install hoses at boom/stick connection.*




- * **There may be still some pressure in the system. Therefore be careful when opening the hoses.**



- **There is only one mounting cap for all pins.**


Position	Designation
1	Pin
2	Cap for mounting
3	Final cap
4	Nut for mounting the final cap
5	Nut for mounting the whirl
6	Safety bolt
7	Hole for the cotter pin
8	Cotter pin



Z 20950


2.10.2 Bullclam Bucket Attachment (Z 20950; Z 20951; 20952)

1. Hook up bucket cylinders that way that rod side shows approx. 45° up to the bearings at the boom.
2. Align the rod eyes with borings at the boom.
3. Install pin (1).
4. Install axle stirrup (2).
5. Install shackle (3) with washer (4) and bolt (5).




Z 20951

6. Lift the stick.
7. Lift the stick to the bearing position stick to the boom.
8. Lower the stick until stick and boom borings are aligned.
9. Install pin (1), stirrups (2), Plate (3); washers (4) and bolts (5).
10. Lower the stick by means of crane and place lower end onto a pile of wood.



Z 20952

11. Hook up stick cylinder to chain pull and remove transport fastening.
12. Lower stick cylinder by means of chain pull and extend cylinder rod. Align with bearing at stick.
13. Install pin (1), plates (2) and washers (3) with bolts (4).



Z 23005

2.11 Assembly of the bucket to the stick

2.11.1 Assembly of the backhoe to the stick (Z 23005)

Position	Designation
1.	Pin
2.	Cap for mounting
3.	Final cap
4.	Nut for mounting the final cap
5.	Nut for mounting whirl
6.	Safety bolt
7.	Hole for the cotter pin
8.	Cotter pin

Installing of this kind of pins:


1. Secure the thread with the mounting cap.
2. Install the pin.
3. Remove the mounting cap.
4. Install a whirl (M20) in the nut (5).
5. Lift the Final cap (3) with a crane, tilt it and turn it on the pin(1) by using the nut (4) (M30).
6. Secure the cap as shown with the bolt (6).
7. Secure the bolt (6) with the cotter pin (8).



- **There is only one mounting cap for all pins.**



- **For further information about the standard tooth system refer to Service Bulletin AH03510.**




Z 20953

2.11.2 Assembly of the bullclam bucket to the stick (Z 20953)

1. Place the rear wall as shown on the ground.
2. Lift the attachment and retract the stick cylinders until the stick is in a vertical position.
3. Move the excavator to the bucket.
4. Align the bores of the stick with the bores of the bucket.
5. Push the pins (1) from (A) to (B) so far that the axle stirrup (2) can be installed.
6. Install the parts (3; 4 and 5). Tighten bolts.
7. By moving and extending the bucket cylinders align the cylinder eyes with the bores of the bucket.
8. Now push pins (7) from outside to inside so far that axle stirrup (6) can be installed.
9. Secure the bolts with parts (8; 9 and 10). Tighten bolts.








- For mounting of the pin seals please refer to page 65.



Z 20954

10. Place the clam shell into the position as shown.
Align the rear wall borings by moving boom, stick and bucket cylinder with the clam borings.
11. Install pins (5) and lock catch (3 and 4).
12. Extend clam cylinder to align them with borings in the clam.
Install pins (1) and lock them with catch (2 and 3).
13. Connect all hose lines to the bucket cylinders and to the clam cylinders in the rear wall.
14. Connect all grease lines to the bucket and ensure that all grease points are greased before machine is put into operation



Z23006

2.12 Mounting of the Pin Seals


2.12.1 Backhoe (Z 23006)

Position	Designation
02; 06; 11; 15	seal ring
03; 07; 12; 16	upper ring half
04; 08; 13; 17	lower ring half
05; 10; 14	seal fixing
20; 21; 22	bolt

The illustration shows the mounting places of the one piece design seals.



- **Fill the groove of the fixing halves with grease before installing.**
- **Proper functioning of the seal is only established in case of an intact seal ring.**




Z 21963

2.12.2 Bullclam bucket (Z 21963)

The illustration shows the mounting places (A, B; C) of the one piece design seals of the bullclam bucket attachment.

Mounting procedure (For example place “B”)

1. Insert both seals (1).
2. Assemble the stick and the rear wall as described on pages before.
3. Install both fixing halves (2) over the seal ring and tighten bolts (3).



Z24031

2.13 Putting the Central Lubrication System into operation (Z 24031)

In order to ensure adequate pre-lubrication of all attachment bearings. It is necessary to manually lubricate the attachment bearings by applying a grease gun to the grease fittings on each grease injector.

To this, remove protection cap (3) and press in grease until a grease collar appears at the connected bearing.



Be sure to repeat the procedure until all pivot bearings of the attachment and cylinder bearings are lubricated.



- **Before handing over the excavator to the customer the first PM Clinic Service has to be carried out according to the Inspection Procedure Manual.**

In order to keep the excavator in first-class operating condition use only genuine Komatsu Mining Germany replacement parts. The use of any part other than the genuine parts releases the Komatsu Mining Germany for any guarantee.

2.14 Standard Application Torque Chart
2.14.1 Metric standard thread

Bolt size (mm)	Wrench size (mm)		Tightening torque MA (Nm)		
			8.8	10.9	12.9
M 8	6	13	21	31	36
M 10	8	17	43	63	73
M 12	10	19	74	108	127
M 14	12	22	118	173	202
M 16	14	24	179	265	310
M 18	14	27	255	360	425
M 20	17	30	360	510	600
M 22	17	32	485	690	810
M 24	19	36	620	880	1030
M 27	19	41	920	1310	1530
M 30	22	46	1250	1770	2080
M 33	24	50	1690	2400	2800
M 36	27	55	2170	3100	3600
M 39		60	2800	4000	4700
M 42	32	65	3500	4950	5800
M 45		70	4350	6200	7200
M 48	35	75	5200	7500	8700
M 52		80	6700	9600	11200
M 56	41	85	8400	12000	14000
M 60		90	10400	14800	17400
M 64	46	95	12600	17900	20900
M 68		100	15200	21600	25500



The torque indications on the chart attached are valid only when the bolts are manufactured according to DIN.

Threads and bolt heads must be lubricated carefully with grease KP2K.

The surfaces of contact which should be screwed together have to be free of grease.

Diverging torques: Bolts at excavator slew rings (see Service Bulletin AH00511a)

2.14.2 Metric fine thread

Bolt size (mm)	Wrench size (mm)		Tightening torque MA (Nm)		
			8.8	10.9	12.9
M 8x1.00	6	13	23	33	39
M 10x1.00	8	17	48	70	82
M 12x1.25	10	19	81	119	139
M 14x1.50	12	22	127	187	219
M 16x1.50	14	24	191	280	330
M 18x2.00	14	27	270	385	450
M 20x2.00	17	30	380	540	630
M 22x2.00	17	32	510	720	850
M 24x2.00	19	36	680	960	1130
M 27x2.00	19	41	990	1410	1650
M 30x2.00	22	46	1380	1960	2300
M 33x2.00	24	50	1850	2650	3100
M 36x3.00	27	55	2300	3250	3850
M 39x3.00		60	3000	4200	4950
M 42x3.00	32	65	3750	5300	6200
M 45x3.00		70	4600	6600	7700
M 48x3.00	35	75	5700	8100	9500
M 52x3.00		80	7300	10400	12100
M 56x4.00	41	85	8900	12600	14800
M 60x4.00		90	11000	15600	18300
M 64x4.00	46	95	13300	19000	22200
M 68x4.00		100	16100	22900	27000

The torque indications on the chart attached are valid only when the bolts are manufactured according to DIN.


Threads and bolt heads must be lubricated carefully with grease KP2K.

The surfaces of contact which should be screwed together have to be free of grease.


Diverging torques: Bolts at excavator slew rings (see Service Bulletin AH00511a).

2.14.3 Torque Chart for Flange Joints

Example of assembly 1




Example of assembly 2




Torques:

M12 - 074 Nm
M14 - 118 Nm
M16 - 179 Nm
M20 - 360 Nm

Example of assembly 3



Example of assembly 4



Torques:

M12 - 108 Nm
M14 - 173 Nm
M16 - 265 Nm
M20 - 510 Nm



- Service Information -
Buscherhofstr. 10
40599 Düsseldorf

Phone +49 (0)211 7109 0
Fax +49 (0)211 74 33 07